

### STC SPECIFICATION SHEET

**FAA STC:** ST02710AT

**Master Drawing List:** 23411-MDL

**Aircraft:** Boeing 767-200/-300

**Configuration:** N/A

#### In-Flight Cabin Video Surveillance System

**Mod. Order:** N/A

**AFMS:** 23411-AFMS

**Master Kit List:** 23411-MKL

**ICA:** N/A

**Summary:**

The In-Flight Cabin Video Surveillance System Installation consist of mounting one camera directly over the cockpit entrance and other camera units mounted throughout the passenger compartment. The Video Control Display Unit is designed to mount in the pedestal or the overhead instrument panel.

**Estimated Electrical Installation Time:** 64 Man Hours

**Installation Kit Lead Time:** 6-8 Weeks

**Estimated Structural Installation Time:** 32 Man Hours

**Equipment:**

Items	Qty	Part Number	Source
Video Control Display Unit	1	VCD14-XY	ASG, Inc.
Camera	4	ICU136-XXX	ASG, Inc.
Housing - Camera Mount Housing – Wedge	3	300-2341176-1-01	ASG, Inc.
Cover Stop - Camera Mount Housing – Wedge	3	300-2341176-1-02	ASG, Inc.
Back Plate - Camera Mount Housing – Wedge	3	300-2341176-1-03	ASG, Inc.
Mount Block - Camera Mount Housing – Recessed	1	300-2341176-5-01	ASG, Inc.
Cover Plate - Camera Mount Housing - Recessed	1	300-2341176-5-02	ASG, Inc.
Crew Alert Switch	2	AML21CBA2AA	ASG, Inc.

**FAA:PMA Installation Kit:**

Items	Qty	Part Number
Surveillance System Installation Kit	1	2341176K-1